

PROJECT: DMPS Brody Middle School Chiller Replacement	PROJECT NUMBER: 20-104	DATE: November 6, 2020
---	------------------------	------------------------

NOTE { *THIS ADDENDUM HAS BEEN ISSUED TO MODIFY AND/OR INTERPRET THE BIDDING DOCUMENTS, INCLUDING THE DRAWINGS AND SPECIFICATIONS. UNLESS OTHERWISE INSTRUCTED. THE INFORMATION CONTAINED ON THE ADDENDUM SHALL TAKE PRECEDENCE OVER ANYTHING CONTRARY ON THE ORIGINAL BIDDING DOCUMENTS AND SHALL BE HEREINAFTER CONSIDERED AS A PARTY OF THE BIDDING DOCUMENTS.*

**SPECIFICATIONS**

SECTION 23 21 23 – HYDRONIC PUMPS

- 1. Part 3.02 Installation
  - A. **REVISE** item K to read “Base mounted pumps shall have a suction diffuser at pump intake.”

**DRAWINGS**

M101 – MECHANICAL PLAN

- 1. **ADD** Pipe Sizes on intake and discharge of 6” to both chilled water pumps, PCWP-1 & PCWP-2, then transition to existing 8” main after piping accessories.
- 2. **ADD** Pipe Sizes on intake and discharge of 6” to both condenser water pumps, CDWP-1 & CDWP-2, then transition to existing 8” main after piping accessories.

**VENDOR APPROVALS**

SECTION 23 0548 – VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

- 1. Flexible Pump Connector
  - A. Metraflex

**ATTACHMENTS**

NO ATTACHMENTS.