



Des Moines Public Schools

Q8578Prospect Support Center Exterior Insulation

An addendum has been issued for this quote opportunity.

Requests for clarification are due Wednesday, November 11, 2020 1:00:00 PM

Quote are due Thursday, November 19, 2020 3:00:00 PM

Visit this bid on our website at <https://dmschools.procureware.com/Bids/8d40650d-66b8-47ee-b18a-113998d22222> to view the addendum.



**DES MOINES PUBLIC SCHOOLS
PROSPECT ROAD SUPPORT
FACILITY
QUOTE Q8578**

ADDENDUM NO. 1 – November 13, 2020

NOTE: Firms quoting this project shall recognize the receipt of this addendum on the quote form.

- Item 1: Delete all references to electrical work, with exception of electrical work required to remove and relocate mechanical heating/cooling units. Owner will coordinate electrical work associated with relocation of existing wall-mounted junction boxes and outlets, under separate contract, prior to start of this work. Drywall contractor to provide information of depth of fur out.
- Item 2: Contractor shall plan for work to be completed in two phases. The first will address the ground floor work areas. The second, to begin immediately following the first phase, will include all in-scope work on the building's second floor. All detailed sequencing shall be coordinated with the Owner's Representative.
- Item 3: CLARIFYING NOTE: A question was raised during the prebid meeting regarding a detail to return drywall to the face of the existing frame. The drywall is not to return to the face of the window frame. Finish exposed drywall edges flush with the edge of brick to permit existing window coverings to be reused. Coordinate final detailing, as required, with Owner's Representative in the field.

END OF ADDENDUM