

Addendum #2

General Construction
Mechanical Construction
Electrical Construction

Project Title DMPS Hoover High School Locker Room Renovation

Hoover High School
4800 Aurora Avenue
Des Moines, Iowa 50310

Owner Des Moines Independent Community School District
2100 Fleur Drive
Des Moines, Iowa 50321

Architect Roseland Mackey Harris Architects PC
1615 Golden Aspen Drive, Suite 110
Ames, Iowa 50010
Ph: 515-292-6075

*Mechanical &
Electrical Engineer* Brewer Engineering Consultants, PLC
905 Washington Ave SE
Bondurant, Iowa 50035

Issue date March 31st, 2021

Bid date **Wednesday, April 6th, 2021 at 3:00 pm**

Addendum #2 contains 1 item.

ADDENDUM NO. 2

Issued March 31st, 2021

To all General contract bidders on the Work titled: DMPS Hoover High School Locker Room Renovation. The proposed Contract Documents are modified as follows:

DRAWINGS.

ITEM 1. ADDENDUM NO. 2

Refer to the Drawings; All accessible water closets and shower stalls shall be equipped with grab bars to make them ADA compliant. The following quantities identify the water closets and shower stalls requiring grab bars.

1st Floor Locker Room: Two (2) Water Closets; Two (2) Shower Stalls.

1st Floor PE Locker Room (Under Alternate #1): One (1) Water Closet; One (1) Shower Stall.

2nd Floor Locker Rooms: Two (2) Water Closets; Two (2) Shower Stalls.

Accessory Information:

Water closets receive; One (1) 18" Vertical grab bar, One (1) 42" Horizontal grab bar, and One (1) 36" Horizontal grab bar. (Refer to the specifications Section 10 2800 TOILET, BATH, AND LAUNDRY ACCESSORIES, Part 2.04, Subparagraph B. Grab Bars: Stainless Steel, smooth surface.)

Shower stalls receive; One (1) continuous horizontal grab bar (type: Bobrick B-6861), and One (1) Vertical grab bar (type: Bobrick B-6806x18).

END OF ADDENDUM NO. 2